

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21162-00-00
Spot: NESENV Sec/Twnshp/Rge: 8-18S-10W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BECK B Well #: 1
County: RICE Total Vertical Depth: 3271 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. D/B/A TE-PE OIL &
Address: PO BOX 522
CANTON, KS 67428

PROD Size: 5.5 feet: 3262 100 SX CMT
SURF Size: 8.625 feet: 256 175 SX CMT

\$ 106³¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2005 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Sand perfs to 2900' and put 5 sxs cmt on top. Cut off casing. Pull to 1250' and pump 35 sxs; pull to 900' and pump 35 sxs;
Plugging pull casing to 310'; and circ cmt to surf.
Method:

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 03/28/2005 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2900' and put 5 sacks of cement on top. Cut off casing at 1580'. Pulled to 1250' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 900' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 310' and circulated cement to surface.

Perfs:

Top	Bot	Thru	Comments
3190	3193		
3021	3028		
2957	2960		

RECEIVED
KCC DISTRICT #2

APR 14 2005

WICHITA, KS

RECEIVED

APR 26 2005

KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 4.26.05
2005061461