

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21179-00-01  
Spot: SWSESE Sec/Twnshp/Rge: 3-25S-9W  
380 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BONTRAGER Well #: 1-OWWO  
County: RENO Total Vertical Depth: 4005 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 4003 175 SX  
SURF Size: 8.625 feet: 231 150 SX

#130'16

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/07/2005 2:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/07/2005 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3790' and put 5 sacks of cement on top. Cut off casing at 2600'. Pulled to 1425' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 825' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 280' and circulated cement to surface.

Allied Cement #20066  
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3840	3848		
<b>RECEIVED KCC DISTRICT #2 APR 11 2005 WICHITA, KS</b>			
<b>RECEIVED APR 26 2005 KCC WICHITA</b>			

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 4-26-05  
INV. NO. 2005061462