

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20303-00-00  
Spot: N2SWSW Sec/Twnshp/Rge: 8-21S-6W  
990 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: WALSTEN E Well #: 2  
County: RICE Total Vertical Depth: 3522 feet

Operator License No.: 8917  
Op Name: GUSTUS, DEAN DBA JD PRODUCTION  
Address: 701 MAIN  
GENESE0, KS 67444

PROD Size: 5.5 feet: 3515 50 SX CMT  
SURF Size: 8.625 feet: 200 150 SX CMT

*\$ 114<sup>47</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2005 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: Sand open hole to 3465' - 3470' and put 5 sxs cement on top. Cut off casing; pull to 1000'; and pump 35 sxs. Pull casing to 600' and pump 35 sxs. Pull casing to 250' and circ cement to surf.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/31/2005 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3465' and put 5 sacks of cement on top. Cut off casing at 1950' and applied stretch. Casing parted at approx 750' and pumped 20 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 250' and circulated cement to surface.

Copeland #24958

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3522			<b>RECEIVED KCC DISTRICT #2 APR 19 2005 WICHITA, KS</b>
			<b>RECEIVED APR 26 2005 KCC WICHITA</b>

Remarks:

Plugged through: CSG

District: 02

Signed

*Virgil Clothier*  
(TECHNICIAN)

**INVOICED**  
DATE 4.26.05  
INV. NO. 2005061463