

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22412-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 5-34S-2E  
1650 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: MCCLASKEY Well #: 1  
County: SUMNER Total Vertical Depth: 3874 feet

Operator License No.: 3954  
Op Name: JAED PRODUCTION CO., INC.  
Address: PO BOX 902  
ARKANSAS CITY, KS 67005

CIBP Size: 5.5 feet: 3080  
PROD Size: 5.5 feet: 3874 150 SX  
SURF Size: 8.625 feet: 291 150 SX

#125<sup>91</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/07/2005 10:00 AM  
Plug Co. License No.: 3954 Plug Co. Name: JAED PRODUCTION CO., INC.  
Proposal Rcvd. from: JAY WARREN Company: JAED PRODUCTION CO., INC. Phone: (620) 442-0826

Proposed Perfs: 3053' - 3057' and 3828' - 3838' CIBP 3080'  
Plugging sand to 3000' & 5 sx cmt  
Method: rec casing  
circ cmt from 350' - 0'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/07/2005 11:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 3000' and capped with 5 sacks of cement.  
Recovered casing from 2045'. Ran 2" tubing to 364' and circulated cement to surface.

Consolidated Cement

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3828	3838		SPF
3053	3057		SPF

RECEIVED  
KCC DISTRICT #2

APR 14 2005

WICHITA, KS

RECEIVED

APR 26 2005


KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

INVOICED  
DATE 4-26-05  
INV. NO. 2005061464