

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21675-00-00
Spot: NESWNE Sec/Twnshp/Rge: 10-27S-7W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WALLACE Well #: 3
County: KINGMAN Total Vertical Depth: 4187 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PROD Size: 5.5 feet: 3985 210 SX CMT
SURF Size: 8.625 feet: 300 200 SX CMT

#136⁰⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/30/2005 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Sand to 3740' & 5 sx
Plugging Perfs 3794'-3812'
Method: 1150' & 35 sx
600' & 35 sx
350' & circ cmt 0'

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 03/30/2005 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 3640' and capped with 5 sacks of cement. Recovered casing 2525'. Pulled to 1150' and spotted 35 sacks of cement. Pulled casing to 600' and spotted 35 sacks of cement. Pulled casing to 350' and circulated cement to 0'.

Allied #20388

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3794	3812		

**RECEIVED
KCC DISTRICT #2
APR 14 2005
WICHITA, KS**


**RECEIVED
APR 26 2005
KCC WICHITA**

Remarks:

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
DATE 4.26.05
INV. NO. 2005061468