

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-25489-00-00
Spot: SW SENE Sec/Twnshp/Rge: 16-26S-18E
3082 feet from S Section Line, 931 feet from E Section Line
Lease Name: MCFARREN Well #: 15
County: ALLEN Total Vertical Depth: 746 feet

Operator License No.: 31488
Op Name: GEORGE, MARK
Address: 817 "C" STREET
LEROY, KS 66857

PROD Size: 2 feet: 740
SURF Size: 7 feet: 20

35⁰⁰

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/15/2005 1:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 740' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 04/15/2005 2:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 700. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

APR 20 2005 CPT

CHANUTE, KS

RECEIVED
APR 25 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

INVOICED

DATE

4.25.05

REF. NO.

2005041454