



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-1879 - 05159-00-020

RECEIVED  
STATE CORPORATION COMMISSION

MAY 4 - 1966  
05-04-1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellinger of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Dellinger guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Company,

Complete Address: Box #405, Chase, Kansas.

Lease Name: J. E. Leonard Well No. 4

Location: CSW-SE-NW Sec. 12 Twp. 6 Rge. (E)(W) 27

County Sheridan Total Depth 3899 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dellinger was instructed to plug the well as follows:

280' --- 8 5/8" Surface pipe, cement circulated with 280 Sx.  
3897' --- 6" OD Production casing cemented with 300 Sx. No plug back nor perforations.

Sand well back to 3850' and set 5 Sx. cement with dump bailer.  
Pull 6" casing to 600' and circulate heavy gel mud. Pull 6" to 540' and displace 20 Sx. cement thru 6". Pull 6" to 210' and displace 20 Sx. cement thru 6". Pull 6", set rock bridge at 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent