



13-179-09260-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1974  
12-9-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Wright of Continental Oil Company has this date requested permission to plug the following described well:

Mr. Wright guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma

Lease Name: Adell L-KC Unit Well No. 101

Location: NE-NE-SE Sec. 11 Twp. 6 Rge. (S)(W) 27

County: Sheridan Total Depth 3885' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wright was instructed to plug the well as follows:

240'--10 3/4" Surface casing, cement circulated with 240 Sx.  
3883'--6" OD Production casing cemented on bottom with 300 Sx. Well  
plugged back to 3859'. Top of perforations @ 3636'.

Push plug to 3630', sand back to 3590' and set 5 Sx. cement with dump  
bailer. Pull 6" casing and squeeze well with 5 sacks hulls, 45 sacks  
gle and 190 Cu. Ft. cement, staged.

Very truly yours,

*H. G. Nichols*  
Conservation Division Agent