

15-179-05291-00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 - 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dwight Dellinger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Dellinger guarantees payment of the plugging fee.

Operator's full Name: Knight Casing Pulling Company,

Complete Address: Box # 405, Chase, Kansas.

Lease Name: B. H. Boutz Well No. 2

Location: CNE-SW-NW Sec. 2 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3793 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dellinger was instructed to plug the well as follows:

240' --- 10 3/4" surface pipe, cement circulated with 240 Sx.
3792' --- 6" OD production casing cemented with 300 Sx. Top perforations from 3670' to 3730'.

Push plug to 3650' sand back to 3600' and set 5 Sx. cement with dump bailer. Pull 6" to 600' and circulate heavy gel mud, pull 6" to 540' and displace 20 Sx. cement thru 6". Pull 6" to 210' and displace 20 Sx. cement thru 6". Pull 6", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent