

State of Kansas



15-179-05621-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67212

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1974

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Wright of Continental Oil Company has this date requested permission to plug the following described well:

Mr. Wright guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name: Adell L-KC Unit Well No. 403

Location: NE-NE-SE Sec. 3 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 3824 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wright was instructed to plug the well as follows:

238'--103/4" Surface casing, cement circulated with 240 Sx.  
3823'--6" OD Production casing cemented on bottom with 300 Sx. Well  
plugged back to 3793'. Top of perforations @ 3568'.

Push plug to 3550', sand back to 3510' and set 5 Sx. cement with dump  
bailer. Pull 6 1/2 casing and squeeze well with 5 sacks hulls, 45 sacks  
gel and 190 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols  
Conservation Division Agent