

15-179-30065 00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12-13-65

LEASE NAME Ade11 LKC

WELL NUMBER 102

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 6S RGE. 27 XXXXr(W)

COUNTY Sheridan

Date Well Completed 12-13-65

Plugging Commenced 1-18-89

Plugging Completed 1-23-89

LEASE OPERATOR Conoco Inc.

ADDRESS 3817 N.W. Expressway, Oklahoma City, OK

PHONE# (405) 948-3100 OPERATORS LICENSE NO. 5916

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-16-88 (date)

by District IV (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing -K.C. Depth to Top 3675 Bottom 3861 T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing - K.C.	Injection	Surf.	237	8 5/8"	232	
		Surf.	3898	5 1/2"	3930	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
RIH w/2 7/8" tbg and tagged at 2070'. Fluid level 600' from surf. Pumped 50' sx econolite 50' sx C1 "A", 14' sx econolite (51 bbls cmt slurry). 18.5 bbls to break circ. Pulled 48' tbg. 2 7/8" tbg. Pumped 20' sx econolite & started circ. POOH tbg & pumped 20' sx ecolite at 200 psi. SI (154' sx total). Pumped 146' sx ecolite down surf pipe. SIP-50psi. Topped well off w/2 1/2 yards common cmt. Cut & capped csg. 4' BGL & cleaned & restored location. KCC Rep.-Carl Goodrow.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Halliburton Services

Address 600 Colorado Derby Bldg., Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco Inc.

STATE OF Oklahoma COUNTY OF Oklahoma

Chris J. Dodson (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Chris J. Dodson

(Address) 3817 N.W. Expressway

SUBSCRIBED AND SWORN TO before me this 15 day of March, 19 89

Candym Driscoll
Notary Public

My Commission Expires: 7/22/92

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1989
3-16-89
CONSERVATION DIVISION
Wichita, Kansas