


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Sheridan County. Sec. 12 Twp. 6 Rge. 27 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines. 2310' FNL & 1650' FWL
Lease Owner Knight Casing Pulling Company
Lease Name J. E. Leonard (Adell Lansing KC Unit 20) Well No. 4
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-25-66 _____ 19____
Plugging completed 4-27-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3899 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	None
				6"	3897'	1118'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3895', sanded hole to 3850' and dumped 5 sacks of cement @ 3850' with dump bailer. Pulled 6" casing to 600' and circulated with 20 sacks of gel mud. Pulled 6" casing to 540' and pumped in 20 sacks of cement. Pulled 6" casing to 200' and pumped in 20 sacks of cement. Pulled balance of 6" casing, set rock bridge @ 35' and capped well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
04-29-1966
APR 29 1966
CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1966

My commission expires May 20, 1968 Notary Public.