

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

15-179-05263-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1977
8-15-77
CONSERVATION DIVISION
Wichita, Kansas

Lease Owner Continental Oil Company
Address 3535 NW 58th Street, Oklahoma City, Okla. 73112
Lease (Farm Name) Adell Lansing KC Unit Well No. 501
Well Location 330' FNL & 1650' FWL ^{NNW/NE NW} Sec. 11 Twp. 6S Rge. (E) 27 (W)
TD 3805'
County Sheridan Total Depth PB 3730' Field Name Adell
Oil Well Gas Well Input Well SWD Well Rotary D & A
Well Log filed with application as required Yes
Date and hour plugging is desired to begin Will notify later

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Mr. J. D. Wright Address P.O. Box 361, Plainville, Kansas 67663

Plugging Contractor Unknown License No. _____
Address _____

Invoice covering assessment for plugging this well should be sent to:
Name Mr. H. S. Miles
Address P.O. Box 267, Great Bend, Kansas 67530

and payment will be guaranteed by applicant or acting agent.

Signed: J. S. Cary
Applicant or Acting Agent
Adm. Supervisor
Date: August 11, 1977



15-179-05263-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

August 15, 1977

WELL PLUGGING AUTHORITY

Well No.	501
Lease	Adell Lansing KC Unit
Description	NW NE NW Sec. 11-6-27W
County	Sheridan
Total Depth	3805
Plugging Contractor	Unknown


Continental Oil Company
3535 NW 58th Street
Oklahoma City, Oklahoma 73112

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above named well.

cc H. S. Miles, Great Bend, KS 67530

Adell Lansing KC Unit No. 501

WELL RECORD
A.M. Bouts Well No. 1

15-179-05263-00-00

Date Spudded: May 20, 1944
Drlg. Completed: June 6, 1944
Potential taken: August 25, 1944
Loc: 330'S and 990'W of N/4 corner of Sec. 11, T6S, R27W, Sheridan County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	6	Rock	2200	2443	Broken Lime
6	60	Shale	2443	2630	Shale & Shells
60	75	Sand	2630	2837	Lime
75	170	Shale	2837	2895	Broken Lime
170	210	Shale & Shells	2895	3378	Lime
210	250	Broken Lime	3378	3454	Broken Lime
250	2017	Shale & Shells	3454	3760	Lime
2017	2130	Broken Lime	3760	3780	Shale
2130	2200	Lime	3780	3805	Lime

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1977
8-15-77

CONSERVATION DIVISION
Wichita, Kansas

Elevation 2575'
Top of Kansas City Lime 3603'

Ran 240' of 10 3/4"OD 28# 3Gauge Armco Spiral Weld casing; set at 238'; cemented with 240 sacks of Universal Portland cement (Halliburton method).

Ran 3763'6" of 6"OD 18# 8RT grade "H-40" Electric Weld casing; ran 6"OD 8RT "Larkin" male and female float collar and 6"OD 8RT "Larkin" guide shoe; set at 3738'; cemented with 300 sacks of Lone Star Portland cement (Halliburton method).


- 6/11/44 - Perforated 6"OD casing with 35 shots, from 3690' to 3708', with Lane-Wells gun perforator - hole filled 600' with water.
- 6/13/44 - Dumped 5 sacks of Portland Dewey cement on bottom, plugging back to 3694'.
- 6/14/44 - Dumped 2 sacks of Monarch cement on bottom, plugging back to 3682'. Cement did not set. Cleaned out cement.
- 6/15/44 - Perforated casing with 11 shots, from 3659' to 3669', with Lane-Wells gun perforator - hole filled 75' with water, no oil, in 20 minutes. Bailed hole dry.
- 6/18/44 - Dumped 7 sacks of Portland Ideal cement on bottom, plugging back to 3647'. Cement did not set. Cleaned out cement and dumped 3 more sacks.
- 6/23/44 - Drilled out cement to 3673'.
- 6/26/44 - Perforated 6"OD casing with 36 shots, from 3605' to 3628', with Lane-Wells gun perforator - hole filled 1100' with oil in 1 hour, and 2600' with oil in 8 hours.

8/25/44 - Established 24 hour physical potential of 587 bbls. oil and 12 bbls. water.

P.B.T.D. 3673' in Kansas City Lime - producing from Kansas City Lime.

Note: Footages calculated from pumping derrick floor level, except formation

I, the undersigned, being first duly sworn upon oath, state that this Well Record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.



F. L. Quinn
District Superintendent

Subscribed and sworn to before me this 18th day of October 1944.

Dennis McQuinn
Notary Public

My commission expires October 21st, 1944.

RDM-HPD
10-18-44
LPC 3
File

William Arnett
10-20-44