

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Rama Operating Co., Inc.

Address: P.O. Box 159 Stafford, Kansas 67578

Phone: (620) 234 5191 Operator License #: 3911

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 4274'

API Number: 15-185-11061-00-00

Lease Name: Camp

Well Number: 2

Spot Location (OOQQ): _____ NW _____ NE

330 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 31 Twp. 25 S. R. 13 East West

County: Stafford

Date Well Completed: 2-14-50

Plugging Commenced: 4-20-05

Plugging Completed: 4-25-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	1298'	None
				7"	4271'	2100'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Set CIBP @3650, dumped 2 sacks cement on top. Cut casing loose @2100', pulled up to 1330', pumped 20 sacks gel, 75 sacks cement w/200# hulls, pulled up to 800', pumped 40 sacks cement w/100# hulls, pulled up to 400', pumped 40 sacks cement w/100# hulls, pulled up to 40' & topped off with 20 sacks cement. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Rama Operating Co., Inc.

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 10th day of May, 2005

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm