

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Dart Cherokee Basin Operating Co. LLC
Address: 3541 County Road 5400, Independence, Ks. 67301
Phone: (620) 331-7870 Operator License #: 33074
Type of Well: D&ADH Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 4/28/05 (Date)
by: Tom Bilyeu (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Mississippi Depth to Top: 1383 Bottom: N/A T.D. 1500

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 205-26009-00-00
Lease Name: H & E Huser Trust
Well Number: B2-30
Spot Location (QQQQ): _____ - SE - SE - NW
3180 Feet from North / South Section Line
2980 Feet from East / West Section Line
Sec. 30 Twp. 30 S. R. 14 East West
County: Wilson
Date Well Completed: 4/27/2005
Plugging Commenced: 4/28/2005
Plugging Completed: 4/28/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	43'	8 5/8"	43'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 1500 feet and mixed 500 lbs. gel in 50 bbls water to gel bore hole. Spot 40 sack 200' cement plug at 1500'
Pull out tubing to 750'. Spot 20 sack 100' cement plug at 750'. Pull tubing out to 350'. Mixed 90 sacks
cement and circulated to surface. Pulled out remaining tubing and topped off with cement. Cut casing off below plow depth
and restored location. A total of 150 sacks of 60/40 Poz Mix cement containing 4% gel were used to plug well.

Name of Plugging Contractor: Consolidated Oil Well Services License #: 31440
Address: 211 W. 14th St., Chanute, Ks. 66720
Name of Party Responsible for Plugging Fees: Dart Cherokee Basin Operating Co. LLC.
State of Kansas County, Montgomery, ss. CHANUTE, KS

Tony Williams (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
My Appt. Expires 5-26-06
(Signature) Tony Williams
(Address) 3541 County Road 5400, Independence, Ks. 67301

SUBSCRIBED and SWORN TO before me this 29th day of April, 20 05
Lisa Shartzer My Commission Expires: 5-26-06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 13 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #3
MAY 2 2005

B...