

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc.
Address: P. O. Box 783188 Wichita KS. 67278-3188
Phone: (316) 691-9500 Operator License #: 4767
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 04-01-2005 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3722' Bottom: 3936' T.D. 3985'

API Number: 15-179-20601-00-00
Lease Name: Robben "P"
Well Number: 1
Spot Location (QQQQ): 110' N of - S/2 - S/2 - NE
2200 Feet from North / South Section Line
1320' Feet from East / West Section Line
Sec. 27 Twp. 8 S. R. 26 East West
County: Sheridan
Date Well Completed: 06/81 7-13-1981 *KCC Bem 5-13-05 RBDms*
Plugging Commenced: 04-20-05
Plugging Completed: 04-20-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	oil/water	3722'	3936'	8.625"	207'	0
				5.50"	3964.5'	0

RECEIVED
MAY 12 2005
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 5.50" csg @ 2200' and 1300' w/ 2 SPF. Ran 2" tbg to 3003'. Pumped 70 sx. 60/40 Pozmix cement w/ 10% Gel & 250# hulls down tbg.
Pulled tbg up to 1926'. Pumped 70 sx. 60/40 Pozmix cement w/ 10% Gel & 200# hulls down tbg. Pulled tbg up to 849'.
Pumped 80 sx. 60/40 Pozmix cement w/ 10% Gel & 200# hulls down tbg, circulated to surface up 5.50" csg. Pulled tbg out of hole.

Loaded and squeezed 5.50" csg w/ 40 sx. 60/40 Pozmix cement w/ 10% Gel, to 300#, shut in at 150#. Pumped 140 sx. 60/40 Pozmix cement w/ 10% Gel & 100# hulls down 8.625" csg, to 250#, shut in at 100#.

Name of Plugging Contractor: Allied Cementing Company Inc. Murfin Drilling License #: 30606
Address: PO Box 31 Russell, KS. 67665

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.


State of Kansas County, Sedgwick, ss.

John Niernberger

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) PO Box 783188 Wichita KS. 67278-3188



SUBSCRIBED and SWORN TO before me this 11 day of May, 20 05

Jennifer L. Foss
Notary Public

My Commission Expires: 10-14-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

B

ALLIED CEMENTING CO., INC. 19272

Federal Tax ID ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

API 15-179-20601-00-00 SERVICE POINT:
OAKLEY

DATE 4-20-05	SEC 27	TWP. 8S	RANGE 26W	CALLED OUT	ON LOCATION 1:00 PM	JOB START 3:00 PM	JOB FINISH 6:15 PM
Robben LEASE	WELL # P-1	LOCATION Studley 1w-25-1w			COUNTY SHERIDAN	STATE KS	

OLD OR NEW (Circle one)

CONTRACTOR MURFIN DRILLING CO.	OWNER SAME
TYPE OF JOB OLD HOLE	CEMENT
HOLE SIZE 5 1/2"	T.D. DEPTH
CASING SIZE 2"	DEPTH 3003'
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

EQUIPMENT

PUMP TRUCK # 191	CEMENTER TERRY	HELPER WAYNE
BULK TRUCK # 386	DRIVER JARRON	
BULK TRUCK #	DRIVER	

AMOUNT ORDERED	400 SKS 60/40 POZ 1026 EL
	800# HULLS
COMMON	240 SKS @ 10% = 2400
POZMIX	160 SKS @ 4% = 752
GEL	34 SKS @ 14% = 476
CHLORIDE	@
ASC	@
	@
	@
	@
	@
	@
HULLS	750# @ 21% = 15750
	@
	@
	@
	@
HANDLING	442 SKS @ 16% = 70720
MILEAGE	64 PER SK 1 MELE = 1458
TOTAL	59513

REMARKS:

MIX 70 SKS CEMENT WITH 250# HULLS AT 3003'
 MIX 70 SKS CEMENT WITH 200# HULLS AT 1926'
 MIX 80 SKS CEMENT WITH 200# HULL AT 849' CIRCULATE TO SURFACE
 Hook ON TO 5 1/2" MIX 40 SKS CEMENT
 MAX PSI 200 SHUT IN 150 PSI Hook ON BACKSIDE
 MIX 140 SKS CEMENT WITH 60# HULLS MAX PSI 250 SHUT IN 100 PSI HANK YO 4

SERVICE

DEPTH OF JOB	3003'
PUMP TRUCK CHARGE	750
EXTRA FOOTAGE	@
MILEAGE	55 ME @ 5% = 275
MANIFOLD	@
	@
	@

CHARGE TO: RITCHIE EXPLORATION

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL 1025

PLUG & FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE 

PRINTED NAME _____

RECEIVED
MAY 12 2005
KCC WICHITA