

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-10-05 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3453' Bottom: 3901' T.D. 3901'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-01619 - 00 - 00
Lease Name: Rostocil
Well Number: C-5
Spot Location (QQQQ): NW - SE - NW -
3630 Feet from North / South Section Line
3630 Feet from East / West Section Line
Sec. 10 Twp. 9 S. R. 19 East West
County: Rooks
Date Well Completed: 10-27-50
Plugging Commenced: 5-12-05
Plugging Completed: 5-12-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Oil, Water	0'	327'	8 5/8"	327'	0'
	Oil, Water	0'	3513'	5 1/2"	3513'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run open end 2 3/8" tbg to 2501'. Pump 75 sx SMD cmt w/300# hulls. Pull tbg to 1407'. Pump 250 sx cmt w/700# hulls, cmt circ to surface. Pull tbg out of hole. Pump 30 sx cmt down 5 1/2" csg. Cmt circ out 8 5/8", 100 psi max. Top off 5 1/2" and 8 5/8" w/10 sx cmt.
Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: P.O. Box 466, Ness City, KS 67560-0466
Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.
Larry M. Jack

RECEIVED
MAY 18 2005
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS



DESCRIBED and SWORN TO before me, this 16th day of May, 20 05
Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bu