

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company

Address: P.O. Box 2757, Wichita, KS 67201-2757

Phone: (316) 263-3535 Operator License #: 5552

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4-29-05 (Date)

by: David P. Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing Depth to Top: 3198' Bottom: 3441' T.D. 3446'

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-00306-00-00

Lease Name: Rostocil

Well Number: B-1

Spot Location (QQQQ): SW-SW-SW

330 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 3 Twp. 9 S. R. 19 East West

County: Rooks

Date Well Completed: 4-5-50

Plugging Commenced: 5-4-05

Plugging Completed: 5-4-05

KCC
BEN
5-18-05
RBDMS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Oil, Water	0'	286'	8 5/8"	286'	0'
	Oil, Water	0'	3443'	5 1/2"	3443'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Log-Tech and perf 2 holes @ 1450'. Run open end tbg to 1834' and pump 55 sx SMD cement w/o hulls w/no blow on annulus.

Pull tbg to 901'. Pump 55 sx cmt w/500# hulls w/no blow on annulus. Pull tbg to 435'. Pump 70 sx cmt w/300# hulls. Cmt circ. to surface.

Pull tbg out of hole. Hook up to 5 1/2" csg and pump 55 sx cmt w/200# hulls, 150 psi max. SI 5 1/2" w/no psi. Hook up to 8 5/8" and pump 50 sx cmt, 250 psi max. SI 8 5/8" w/50 psi. Topped off 5 1/2" w/30 sx cmt. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382

Address: P.O. Box 466, Ness City, KS 67560-0466


Name of Party Responsible for Plugging Fees: Gore Oil Company

State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack

(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 16th day of May, 20 05

Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 18 2005
KCC WICHITA

Bm