

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-29-05 (Date)
by: David P. Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Lansing Depth to Top: 3212' Bottom: 3457' T.D. 3463'
Arbuckle Depth to Top: 3458' Bottom: 3463' T.D. 3463'
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-01615-00-00
Lease Name: Rostocil B
Well Number: C-1
Spot Location (QQQQ): NW - NW - NW -
4950 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 10 Twp. 9 S. R. 19 East West
County: Rooks
Date Well Completed: 6-30-50
Plugging Commenced: 5-5-05
Plugging Completed: 5-5-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Oil, Water	0'	308'	8 5/8"	308'	0'
	Oil, Water	0'	3457'	5 1/2"	3457'	0'


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run open end 2 3/8" tbg to 1057' & tagged bottom. Hook up tbg & wash down to 1110', couldn't get any deeper. Pump 200 sx SMD cmt w/o hulls. Pull tbg to 880'. Pump 40 sx SMD cmt w/300# hulls. Cmt circ. to surface. Pull tbg out of hole. Hook up to 5 1/2" csg and pump 45 sx cmt w/3sx hulls, 1,000 psi max. Shut in 5 1/2" w/300 psi. 8 5/8" pumped 45 sx cmt, 150 psi max. Shut in 8 5/8" w/100 psi. Top off 5 1/2" w/25 sx cmt. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
Address: P.O. Box 466, Ness City, KS 67560-0466
Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.
Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being that I

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack
(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 16th day of May, 20 05
Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 18 2005
KCC WICHITA

Bm