

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00306-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 3-9S-19W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ROSTOCIL B Well #: 1
County: ROOKS Total Vertical Depth: 3446 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

PKR Size: feet: 3141
PROD Size: 5.5 feet: 3443 125 SX CMT
SURF Size: 8.625 feet: 286 175 SX CMT

\$112⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2005 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPAY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 325 sxs Swift Multi-Density Cement - 1000# hulls.
Open hole arbuckle 3443' - 3446'.
CIBP set at 3420' with one sack cement.
CIBP at 3155'. Bridge at 700'. Ran tubing to 1945' - casing parted below salt section.
No squeeze records. Perf: anhy 1420'. High fluid level.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2005 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 1420'.
Ran tubing to 1834'. Swift Services pumped 55 sxs SMD.
Pulled tubing to 901' - pumped 55 sxs SMD with 500# hulls.
Pulled tubing to 435' - pumped 70 sxs SMD with 300# hulls - cement circulated.
PTOH. Squeezed with 55 sxs SMD cement with 200# hulls.
Shut in one hour.
Cement 400' down - topped off with 30 sxs.
Hooked up to 8 5/8" - pumped 50 sxs SMD.
Max. P.S.I. 300#. S.I.P. 100#.
Total 315 sxs SMD and 1000# hulls.

Perfs:

Top	Bot	Thru	Comments
3197	3396		

RECEIVED
MAY 16 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 5-17-05

NO. 2005061578

Form CP-2/3

MAY 09 2005

