

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20555-00-00  
Spot: NWNWNWSW Sec/Twnshp/Rge: 16-1S-34W  
2330 feet from S Section Line, 4970 feet from E Section Line  
Lease Name: CAHOJ UNIT Well #: 939  
County: RAWLINS Total Vertical Depth: 4375 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 7 feet: 4374 w/525 sxs cmt  
SURF Size: 10.75 feet: 324 w/285 sxs cmt

# 142<sup>19</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/13/2005 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II cement and 1000# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/13/2005 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

10 3/4" surface casing set at 324' w/285 sxs. 7" production casing set at 4374' w/525 sxs.  
TD at 4375' PBTD 4190'.  
Ran tubing to 2500' - pumped 210 sxs cement with 450# hulls.  
Pulled tubing to 1200' - pumped 100 sxs cement with 450# hulls.  
Pulled tubing to 600' - pumped 10 sxs cement - cement to surface.  
Connected to 7" production casing - pumped 5 sxs cement.  
Max. P.S.I. 150#. S.I.P. 0#.  
Connected to 10 3/4" surface casing - pumped 25 sxs cement with 100# hulls.  
Max. P.S.I. 300#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
4247	4252		
4205	4208		
4103	4107		
4063	4070		

RECEIVED  
MAY 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #8065.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

DATE

5-18-05

WV. NO.


2005061589

Form CP-2/3

MAY 16 2005

GETTY OIL COMPANY  
 2705 VINE, UNIT #4 #939 CAHOJ UNIT 16-1-34W  
 HAYS, KS 67601 2330'ESI &  
 CONTR MURFIN DRILLING CO. CTY RAWLINS 310'FWL, SW/4

GEOL \_\_\_\_\_ FIELD CAHOJ \_\_\_\_\_



ELV 3178 KB SPD 7/13/84 CARD ISSUED 10/11/84 IP P 23 BO & 937 BWPD  
 3173 GL LKC 4063-4252 OA

LOG	Tops .....	Depth/Datum	API 15-153-20,555
			10 3/4 " 324/285SX, 7" 4374/525SX
			NO DST'S
TOP .....	3856-	678	MICT - CO, PF (LKC) 4247-52, 4205-08, 4103-07, 4063-70, W/ 4
OREAD .....	3952-	774	SPF, AC 2750G, SWB DWN, GSO, T&R, POP, P 23 BO & 937
DOUG .....	4010-	832	BWPD 9/7/84
LANS .....	4048-	870	
MARM .....	4354-	1176	
PBTD .....	4190-	1012	
RTD .....	4375-	1197	

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

2705 VINE UNIT #4  
 HAYS, KS 67601  
 MURFIN DRILLING CO.