

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-05300-00-01  
Spot: NWNE Sec/Twnshp/Rge: 20-1S-34W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: CAHOJ UNIT Well #: 57  
County: RAWLINS Total Vertical Depth: 4390 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4386 w/200 sxs cmt  
SURF Size: 8.625 feet: 372 w/300 sxs cmt

# 142<sup>68</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2005 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 330 sxs Midcon II cement and 1000# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2005 11:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 372' w/300 sxs. 5 1/2" production casing set at 4386' w/200 sxs.  
TD at 4390'. PBSD 4287'.  
5 1/2" production casing squeezed from 1672' - 2987' with 200 sxs.  
Ran tubing to 2500' - pumped 135 sxs cement with 450# hulls.  
Pulled tubing to 1200' - pumped 70 sxs cement with 450# hulls.  
Cement to surface. Pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 10 sxs cement.  
Max. P.S.I. 450#. S.I.P. 0#.  
Connected to 8 5/8" surface casing - pumped 20 sxs cement.  
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4260	4269		
4244	4246		
4229	4232		
4178	4186		

RECEIVED  
MAY 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #8061.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

DATE 5-18-05

INV. NO. 2005061589

Form CP-2/3

MAY 12 2005

STATE: KANSAS COUNTY: RAWLINS REISSUE OWWO 20-1S-34W  
FIELD: CAHOJ C NW NE  
OPER: TEXACO INC 4620 FSL 1980 FEL SEC  
WELL: 57 CAHOJ UNIT WELL CLASS: DO ELEV: 3184 KB  
API: 15-153-05300-0001 STATUS: OIL-WO  
SPUD: 06/09/86 COMP: 06/09/86  
DTD: 4390 LTD: FTD: MARMATON PBTD: 4287

**LOC:**

IP: COMP 6/9/86, IPP 7 BO, 143 BWPD PROD ZONE- LANSING-KANSAS CITY  
4178-4269 (GROSS) FIRST REPORT & COMPLETION

**OWWO:** OWWO: OLD INFO: FORMERLY SKELLY OIL 2 CAHOJ "G". ELEV: 3184 KB. SPUD  
6/19/60. 8 @ 372, 5 @ 4386. LOG TOPS: TOPEKA 3878. OREAD 3978. LANSING  
4074, MARMATON 4372. OTD 4390. COMP 7/29/60. IPP 116 BOPD, NO WTR. PROD  
ZONE: LANSING-KANSAS CITY 4260-4269.

**PRODUCING INTERVAL:** PERF (LANSING-KANSAS CITY), 4178-4186, 4229-4232,  
4244-4246, 4260-4269.

**OPER ADD:** BOX 2420, TULSA, OK, 74102 PHONE (316) 792-2193;

**CONTR:** NOT RPTD

**WELL ID CHANGES:** API CHGD FROM 15-153-30089-0001;  
REISSUE TO CORR API REPLACES CARD ISSUED 6/17/94