

To: STATE CORPORATION COMMISSION Wichita State Office Bldg. - PLUGGING SECTION 130 S. Market, Room 2078 Wichita, Kansas 67202

KCC BEM 5-13-05 NE NWSWNW Sec/Twp/Rge 31-17-22 E
Per ~~Footage~~ 3704 feet from south section line
4525 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: State of Kansas Fee FundName & Fee Fund Plugging

Address _____

AB oil well Gas Well _____Lease/Well# Kitchen GPS # 03County MiamiWell Total Depth 300 EST. feetProduction Pipe: 2 Size Feet 300 EST.Surface Casing: 10 Size Feet 20 est.

SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service Lic. # 30670Address: 19245 Ford Road Chanute, Ks. 66720Company to plug at: Hour: _____ Day: 23 Month: 3 2005Plugging proposal received from: Mike KepleyCompany Name: Kepley Well Service Phone: 620-433-7196Were: Fill well from TD to surface with portland cement, inside pipe and outside pipe.

Plugging Proposal Received by: _____

Frank GuilfoylePlugging attended by Agent: All Part None _____Operations Completed: Hour: _____ Day: 15 Month: 4 2005Actual Plugging Report: CLEAR LOCATION WITH DOZER. PULL ON 1" AND PACKER. TRY TOWORK PACKER LOOSE. 1" PARTED AT ABOUT 80 FT DOWN. RAN 1" TAP AND SCREWED INTO 1"AND BROKE TAP INSIDE 1" COLLAR. FISH ON 1" WITH OVERSHOT, MOUSETRAPS, AND ANOTHERTAP. DIDN'T GET OUT. BROUGHT IN LEFT-HANDED 1" WITH LEFT-HANDED OVERSHOT. FINALLYGOT OUT 1" TO 200 FT. RUN 1" BACK INSIDE 2" TO 200 FT. WASH DOWN OUTSIDE OF 2" TO 250 FT.PUMP PORTLAND CEMENT TO SURFACE INSIDE AND OUTSIDE 2". PULL PIPE AND TOP OFF ~~RECEIVED~~PUMP TOTAL OF 112 SACKS OF CEMENT. WELL PLUGGED.RECEIVEDAPR 28 2005Remarks: Control # 20050034-003 GPS # 03(If additional description is necessary, use BACK of this form.)KCC WICHITA

I DID observe this plugging.

Signed:

FRANK GUILFOYLE

TECHNICIAN

Bu