

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-30257-00-00  
Spot: NWSWNE Sec/Twnshp/Rge: 27-21S-7W  
*2770* ~~3792~~ feet from S Section Line, ~~2311~~ feet from E Section Line  
Lease Name: STEIERL Well: 1 *083-5-17-05*  
County: RICE Total Vertical Depth: 3473 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3472 75 SX CMT  
SURF Size: 8.625 feet: 219 150 SX CMT

*411287*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2005 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD Company: QUALITY WELL SERVICE, INC. Phone: (316) 727-3410

Proposed Plugging Method: Sand to 3341' and cap with five sacks of cement. Rip pipe for recovery. Pump 35 sacks at 1000'. Pump 35 sacks at 550'. Circulate cement from 270' to surface.

Plugging Proposal Received By: GREG EVES WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/16/2005 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3341' and capped with 5 sacks of cement. Ripped pipe at 1320'. Pulled to 1000' and pumped 35 sacks of cement. Pulled pipe to 550', pumped 35 sacks of cement, and pulled to 270'. One sack of cotton hulls, 11 sacks of gel, and 48 sacks of cement were required to circulate to surface.

118 sacks of 60/40 posmix with 4% gel, 1 sack of cotton hulls, and 11 sacks of gel total

Gressel #5

Perfs:

Top	Bot	Thru	Comments
3410	3418		
<b>RECEIVED KCC DISTRICT #2 APR 20 2005 WICHITA, KS</b>			
<b>RECEIVED MAY 13 2005 KCC WICHITA</b>			

Remarks:

Plugged through: CSG

District: 02

Signed Meg Eves  
(TECHNICIAN)

**INVOICED**

DATE 5-16-05

INV. NO. 2005061566