

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-20625-00-01
Spot: SWSW Sec/Twnshp/Rge: 17-26S-16W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: ELLIS Well #: 1 OWWO
County: EDWARDS Total Vertical Depth: 2283 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

SURF Size: 8.625 feet: 265

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/19/2005 5:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: RIG UP & RUN TUBING TO 1100' & CONDITION THE HOLE WITH GEL & HULLS. PUMP 50 SX CMT AT 1000'. PULL DRILL PIPE TO 290' & PUMP 50 SX CMT. PULL DRILL PIPE TO 40' & PUMP 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 04/19/2005 6:30 PM

WitnessType: COMPLETE (100%)
KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG RAN TUBING TO 1000' CIRCULATE HOLE WITH 20 SX FRESH WATER GEL FOLLOWED BY 50 SX CMT. 2ND PLUG PULL TUBING TO 290' & MIX & PUMP 50 SX CMT. 3RD PLUG PULL TUBING TO 40' & CIRCULATE CMT TO SURFACE.


Perfs:

RECEIVED
MAY 16 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Steve Durrant

(TECHNICIAN)