

3 022718

15.207.19510-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE Lic. # 6372Address: BOX 386, RR4, CHANUTE, KANSAS 66720Company to plug at: Hour: 9:00AM Day: 15 Month: 4 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. 1" PIPE HAD BEEN "LEFT HANDED" FROM THE WELL TO 630'. PROBABLY 1" PIPE REMAINS IN THE WELL FROM 630' TO NEAR T.D.. THE PLUGGING PROPOSAL IS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All _____ Part _____ TECHNICIAN None ☒ XOperations Completed: Hour: 12:30P.M. Day: 15 Month: 4 2005Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 630'. CEMENTWAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" & 8" ANNULUSTO 550'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WASFILLED FROM SURFACE. 214 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 9) (THIS WELL WAS NO.18 ON THE LEASE MAP.)
 (If additional description is necessary, use BACK of this form.)

RECEIVED

APR 28 2005

KCC WICHITA

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
 TECHNICIAN

Bm