

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23190-00-00
Spot: NENESW Sec/Twnshp/Rge: 22-24S-15W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: SUITER Well #: 1
County: STAFFORD Total Vertical Depth: 4215 feet

Operator License No.: 33260
Op Name: THE WARREN CORPORATION
Address: 50 PENN PLACE, SUITE 410
OKLAHOMA CITY, OK 73118

CIBP Size: feet: 4165 WITH 5 SX CMT
PROD Size: 5.5 feet: 4214 WITH 100 SX CMT
SURF Size: 8.625 feet: 340 WITH 250 SX CMT

\$136⁹⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2005 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: CIBP @ 4165' WITH 5 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 55 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2005 12:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 1010'. SET CIBP @ 4165' WITH 5 SX CMT ON TOP. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 390' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 55 SX CMT.

Perfs:			
Top	Bot	Thru	Comments
4214	4215	OH	

RECEIVED
MAY 18 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2650' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

MAY - 9 2005
MD

INVOICED
DATE 5-18-05
INV. NO. 20050615.92

Form 0121