

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01619-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 10-9S-19W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: ROSTICAL C Well #: 5  
County: ROOKS Total Vertical Depth: 3514 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

PROD Size: 5.5 feet: 3513 200 SX CMT  
SURF Size: 8.625 feet: 327 175 SX CMT

*4/14<sup>21</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2005 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 289-1923

Proposed Plugging Method: Ordered out 400 sxs Swift Multi-Density Cement with 1000# hulls.  
Cleaned out 5 1/2" casing to 3483' - circulated a lot formation and sand out.  
Decided to plug.  
Arbuckle perms 3456' - 3462'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/12/2005 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2501'.  
Swift Services pumped 75 sxs Swift Multi-Density cement with 300# hulls.  
Pulled tubing to 1407'.  
Swift Services pumped 250 sxs Swift Multi-Density cement with 700# hulls.  
Circulated cement out both 5 1/2" casing and 8 5/8".  
PTOH. Squeezed with 75 sxs SMD.  
Max. P.S.I. 400#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3453	3901		

RECEIVED  
MAY 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED  
DATE 5-18-05  
JV. NO. 2005061587

MAY 16 2005