

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01615-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 10-9S-19W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ROSTICAL C Well #: 1  
County: ROOKS Total Vertical Depth: 3458 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

PKR Size: feet: 2970  
PROD Size: 5.5 feet: 3457 150 SX CMT  
SURF Size: 10.75 feet: 308 175 SX CMT

#112<sup>39</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/05/2005 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 289-1923

Proposed Plugging Method: Ordered out 350 sxs Swift Multi-Density Cement with 1000# hulls.  
5 1/2" casing set at 3457'. TOC at 2820'. CIBP set at 3155'. Anhy 1416'.  
Bridge at 920'. Clean out to 1067'. Rough casing.  
Run tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/05/2005 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran mule shoe to 1027'. Swift Services cleaned out to 1110'.  
Lost circulation - hard bottom.  
Swift Services pumped 100 sxs Swift Multi-Density cement neat.  
Pulled to 865'. Swift Services pumped 40 sxs SMD with 300# hulls cwc.  
PTOH. Squeezed with 35 sxs.  
Max. P.S.I. 800#. Shut in - slowly dropping. Shut in casing.  
Hooked up to backside and pumped 45 sxs SMD cement.  
Max. P.S.I. 150#. S.I.P. 100#.  
Hooked back on casing - took one barrel to load.  
Pumped 10 sxs SMD cement.  
Max. P.S.I. 1100#. S.I.P. 700#.

Perfs:

Top	Bot	Thru	Comments
3458	3462		
3211	3451		

RECEIVED  
MAY 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 5.18.05

INV. NO. 2005061587

MAY 16 2005