

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21591-00-00
Spot: S2 Sec/Twnshp/Rge: 35-15S-28W
1320 feet from S Section Line, 2640 feet from E Section Line
Lease Name: ROBERTS D Well #: 1-35
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

SURF Size: 8.625 feet: 316'

143⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/11/2005 12:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (620) 793-0834

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE
Date/Time Plugging Completed: 05/11/2005 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 1980' w/25 sxs.
2nd. Plug at 925' w/100 sxs.
3rd. Plug at 366' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

RECEIVED
MAY 18 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

ND

Signed *Pat Staab*
(TECHNICIAN)

INVOICED

DATE 5-18-05
INV. NO. 2005061591

Form CP-2/3

MAY 16 2005