

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-179-20296-00-01

API NUMBER NA

LEASE NAME GLASGOW 'A'

WELL NUMBER 2 SWD

SPOT LOCATION C NE SW

SEC. 21 TWP. 6 RGE. 26 (E or W)

COUNTY SHERIDAN

Date Well Completed 12-30-71

Plugging Commenced 10-28-86

Plugging Completed 10-28-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. ABERCROMBIE, INC.

ADDRESS 801 UNION CENTER, WICHITA, KS. 67202

PHONE # (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well INPUT
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? YES If not, is well log attached? YES

Producing formation LANSING KC Depth to top 3758 bottom 3962 T.D. 3975

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>LANSING KC</u>	<u>WATER</u>	<u>3418</u>	<u>3698</u>	<u>8 5/8</u>	<u>387</u>	<u>NONE</u>
				<u>4 1/2</u>	<u>3975</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged 4 1/2" csg. with 5 sacks Hulls, 115 sacks cement with standing press of 1000#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A. L. ABERCROMBIE, INC. License No. 5393

Address _____

Rt. 1, Box 56, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

E. L. ABERCROMBIE (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E L Abercrombie

(Address) Rt 1 Box 56 Gr. Bend Ks

SUBSCRIBED AND SWORN TO before me this 6th day of November, 1986

Sherrie L. Brooks
Notary Public

Sherrie L. Brooks

My Commission expires: August 21, 1990.

15-179-20296-00-01

CONTRACTOR'S WELL LOG

OPERATOR:	A. L. Abercrombie, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	GLASGOW #2
LOCATION:	C NE SW, Sec. 21-6S-26W Sheridan County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	December 20, 1971
COMPLETION DATE:	December 30, 1971

0	295	Clay, Sand & Rock
295	700	Shale
700	1165	Shale & Shells
1165	1290	Sand
1290	1390	Shale & Shells
1390	1735	Shale
1735	1865	Shale & Shells
1865	2038	Sand
2038	2261	Shale
2261	2293	Anhydrite
2293	2795	Shale & Lime
2795	3794	Lime & Shale
3794	3975	Lime
	3975	Rotary Total Depth

Drilled 389' of 12½" surface hole. Set 8-5/8" surface csg. at 387' K.B. w/275 sx. Sunset cement. Cement circulated. Plug was down at 10:30 p.m. 12-20-71. Set 4½" 11.6# csg. at 3975'. Cemented w/35 sx. 50/50 posmix w/2% gel and 12 lbs. gilsonite per sack and 100 sx. common cement w/10% salt, 1% c.c., 2% gel and friction reducer. Job was complete at 7:45 a.m. 12-30-71.

<u>ELECTRIC LOG TOPS</u>	<u>ELEVATION</u>
Anhydrite 2259 (+ 392)	2651 K.B.
B/Anhydrite 2293 (+ 358)	2649 D.F.
Heebner 3718 (-1067)	2643 G.L.
Toronto 3742 (-1091)	
Lansing 3758 (-1107)	
B/K.C. 3962 (-1311)	
ELTD 3976 (-1325)	

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

NOV 7 1983

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GLASGOW #2, C NE SW, Section 21-6S-26W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr
 President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 11th day of January, 1972.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:

February 10, 1975