

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Big O, LLC
Address: 2820 Paseo Drive Great Bend, Kansas 67530
Phone: (620) 792-2868 Operator License #: 3942

API Number: 15-185-01340-00-00
Lease Name: G. Schmidt
Well Number: 2

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (OOQQ): N/2 - NW - SW
2310 Feet from North / South Section Line
4620 Feet from East / West Section Line
Sec. 6 Twp. 22 S. R. 13 East West

The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

County: Reno
Date Well Completed: 1-13-46
4-8-04
Plugging Commenced: _____
Plugging Completed: 4-12-05

Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 3710

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	558'	None
				5-1/2"	3703'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3400' and 5 sacks cement. Cut hole in casing @840', ran 2-3/8" tubing to 840', pumped 150 sxs. cement w/150# hulls, lost circulation. Tagged cement @900, ran 2-3/8" tubing to 840', pumped 100 sxs. cement w/250# hulls, & circulated & pulled tubing out, topped off w/110 sxs. Plugging Complete. 60/40 6% pos.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Big O, LLC.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 21st day of April, 2005

Irene Herzberg Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 22 2005
KCC WICHITA

[Handwritten signature]