

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Globe Operating, Inc.

Address: Globe Operating, Inc.

Phone: (620) 792-7607 Operator License #: _____

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. 4005'

API Number: 15-155-21,179-00-01

Lease Name: Bontrager

Well Number: 1 OWWO

Spot Location (QQQQ): 50' N . CSW . SE . SE
380 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 3 Twp. 25 S. R. 9 East West

County: Reno

Date Well Completed: _____

Plugging Commenced: 4-5-05

Plugging Completed: 4-7-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	231'	None
				5-1/2"	4003'	2600'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3790' and 5 sacks cement. Cut casing loose @2600', pulled up to 1425', pumped 35 sacks cement w/100# hulls, pulled up to 825', pumped 35 sacks cement w/100# hulls, pulled up to 280' and circulated 120 sacks cement, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
6170

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Globe Operating, Inc.

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) _____

SUBSCRIBED and SWORN TO before me this 21st day of April, 2005

Irene Herzberg My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 22 2005
KCC WICHITA

Bu