

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Shelby Resources, LLC

Address: 5893 Saddle Creek Trail, Parker, CO 80134

Phone: (303) 840-2183 Operator License #: 31725

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 03-10-2005 (Date)

by: Richard Williams (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Topeka Depth to Top: 2937 Bottom: 3141 T.D. Lansing KC Depth to Top: 3178 Bottom: 3401 T.D. Arbuckle Depth to Top: 3428 Bottom: 3435 T.D. 3435

API Number: 15-163-21154-00-00

Lease Name: Lowry

Well Number: #3

Spot Location (QQQQ): S/2 - SE - NW - SW 3960 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 20 Twp. 8 S. R. 19 East West

County: Rooks

Date Well Completed: 12-29-1980

Plugging Commenced: 04-15-2005

Plugging Completed: 04-15-2005

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Lansing KC, 3217-22', 0, 286, 8-5/8", 286, none. Row 2: 0, 3431, 4-1/2", 3431, none.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Brought out 275 sxs. 60/40 poz with 10% gel and 500# hulls. RIH with 2" tubing to 2150'. Circulate cement to surface with 120 sxs. and 400# hulls. Pull tubing. Mixed another 100 sxs. and 100# hulls down casing. Squeezed to 400#. Shut in @ 200#. Tied on to annulus. Mixed 5 sxs. and squeezed to 200#. Rich Williams with KCC District 4 witnessed the plug.

Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 99996

Address: P.O. Box 31, Russell, Kansas 67665-0031

Name of Party Responsible for Plugging Fees: Shelby Resources, LLC

State of Colorado County, Douglas, ss.

Shelby Resources, LLC (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Brian Karlen

(Address) P.O. Box 1213, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 22nd day of April, 20 05

Gale D. Fischer Notary Public My Commission Expires: 11-4-2006

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED APR 25 2005 KCC WICHITA

Handwritten signature