

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shelby Resources, LLC

Address: 5893 Saddle Creek Trail, Parker, CO 80134

Phone: (303) 840-2183 Operator License #: 31725

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 04-03-2005 (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: 3287 Bottom: 3491 T.D. _____
Lansing KC Depth to Top: 3531 Bottom: 3753 T.D. _____
Arbuckle Depth to Top: 3859 Bottom: 3915 T.D. 3915

API Number: 15-065-23051-00-00

Lease Name: Rudman

Well Number: #1

Spot Location (QQQQ): _____ - SW - SW - NW
2310 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 3 Twp. 10 S. R. 21 East West

County: Graham

Date Well Completed: 04-03-2005

Plugging Commenced: 04-03-2005

Plugging Completed: 04-03-2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	220	8-5/8"	220	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Brought out 225 sxs. 60/40 poz with 6% gel and 1/4# flo seal. Plugged well with 25 sxs. @ 3840', 25 sxs. @ 1775', 100 sxs. @ 1075', 40 sxs. @ 275', and 10 sxs. @ 40'. Also put 15 sxs. in rathole and 10 sxs. in mouse hole.

Name of Plugging Contractor: Allied Cementing Co., Inc. Murfin Drilling License #: 30606

Address: P.O. Box 31, Russell, Kansas 67665-0031

Name of Party Responsible for Plugging Fees: Shelby Resources, LLC

State of Colorado County, Douglas, ss.

Shelby Resources, LLC (Employee of Operator) or (Operator) on above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Brian Kender

(Address) P.O. Box 1213, Hays, Kansas 67601

SUBSCRIBED and SWORN TO before me this 22nd day of April, 20 05

Gale D. Fischer My Commission Expires: 11-4-2006
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED
APR 25 2005
KCC WICHITA
KCC
BEM
4-26-05
RBM/S

[Handwritten signature]