

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-21412-0000

LEASE NAME HALL

WELL NUMBER 3-1

1250' FNL Ft. from S Section Line

1250' FEL Ft. from E Section Line

SEC. 1 TWP. 30S RGE. 36W (E) or (W)

COUNTY GRANT

Date Well Completed 5/16/98

Plugging Commenced 4/28/05

Plugging Completed 4/28/05

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

RECEIVED
MAY - 5 2005
KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/10/04, 03/09/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 2973 GL Bottom 3100' T.D. 2905'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2805'	2929'	8 5/8"	640'	0
				5 1/2"	3099'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

4/28 KCC Notified, didn't witness. CIBP @ 2700'. 20' cmt. TOC 2680'. Load hole w/ 23 bbl 9 ppg 36 cp mud 2680'-1645' & 18 bbl mud spacer from 1495'-670' & 80 sx cmt plug from 670'-surface. Pmp 30 sx cmt from 180'-surface. Cut both casings 3' BGL. Weld on trash cover-ID plate.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SUBSCRIBED AND SWORN TO before me this 2nd day of May, 20 05
Deborah Pollock
Notary Public

My Commission Expires: 4/2/09

B...