

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15 055-20123-00-00

LEASE NAME Boyd

WELL NUMBER 1-18

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 18 TWP. 23 RGE. 31W (E) or (W)

COUNTY Finney

Date Well Completed 04/01/75

Plugging Commenced 04/13/05

Plugging Completed 04/13/05

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE (405) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/15/04 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2656 Bottom 2666 T.O. 2750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	359	
				8-1/2	2690	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set: MIRU Allied, pump down 5-1/2" csg w/150# hulls, mix 75 sx cmt., pump 150 #hulls w/cmt, displace 41 bbls, max PSI 700#, left well SI 1 hr. MIRU Rosel, Perf 1295', Allied pump on 5-1/2", did not circ, run CBL from 800' to surf., perf 600', circ, pump 150 sx cmt, did not circ to surf, SIW 200#, wellbore plugged, used total 225 sx cmt, RDMO Allied & Rosel, cut casing off, weld ID plate, fill pit

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 99996

Address P. O. Box 31, Russell, KS 67665 (785) 483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) P.O. Box 18496, Okla. City, OK 73154

RECEIVED  
MAY - 5 2005  
KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 2005  
LUCRETIA A. MORRIS  
Notary Public  
State of Oklahoma  
Commission # 00018352 Expires 11/27/08



# ALLIED CEMENTING CO., INC. 18544

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Oakley

DATE <u>4/13/05</u>	SEC. <u>19</u>	TWP. <u>23s</u>	RANGE <u>31w</u>	CALLED OUT	ON LOCATION <u>7:15 AM</u>	JOB START <u>9:45 AM</u>	JOB FINISH <u>4:15 PM</u>
LEASE <u>Boyd</u>	WELL.# <u>1-18</u>	LOCATION <u>83+6mi N 7E 1/2 S 4w S/4</u>		COUNTY <u>FINNEY</u>	STATE <u>KS</u>		

OLD OR NEW (Circle one)

CONTRACTOR \_\_\_\_\_  
 TYPE OF JOB O, H.P  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 5 1/2 DEPTH 2666  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER Sam  
 CEMENT  
 AMOUNT ORDERED  
470 sks 60/40 + 670 gal  
450 22.5 sks 60/40 + 670 gal

EQUIPMENT

PUMP TRUCK CEMENTER Max  
 # 373-281 HELPER Andrew  
 BULK TRUCK  
 # 386 DRIVER Larry  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

COMMON	<u>135 sk</u>	@ <u>9.55</u>	<u>1289.25</u>
POZMIX	<u>90 sk</u>	@ <u>4.50</u>	<u>405.00</u>
GEL	<u>12 sks</u>	@ <u>13.00</u>	<u>156.00</u>
CHLORIDE		@	<u>156.00</u>
ASC		@	
C.S. Hulls	<u>300 #</u>	@ <u>20.00</u>	<u>60.00</u>
HANDLING	<u>494</u>	@ <u>150</u>	<u>741.00</u>
MILEAGE	<u>5 1/2 @ 1st / mi</u>		<u>2037.75</u>
TOTAL			<u>4689.00</u>

REMARKS:

Hookup to 5 1/2 csg Pump 150# C.S. Hull Mix  
75 sks Cmt with 150# C.S. Hulls in First  
of Cmt. Displace 41 BDL Pressure to  
700 PSI Perf @ 1295 Pressure to 800  
Could not Pump into head log T.O.C 656  
Perf @ 600 Circulate Cmt to  
Surface with 150 sk

SERVICE

DEPTH OF JOB	<u>2666</u>		
PUMP TRUCK CHARGE			<u>700.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>75 mi</u>	@ <u>4.50</u>	<u>337.50</u>
MANIFOLD		@	
TOTAL			<u>1037.50</u>

RECEIVED  
 MAY - 5 2005  
 KCC WICHITA

CHARGE TO: Chesapeake Operating  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Dennis Frick

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS \_\_\_\_\_  
 PRINTED NAME Dennis Frick