

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 03 2005
CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: REX H. CAMBERN
Address: 2332 N. RIDGEFIELD CIR., WICHITA, KS. 67205
Phone: () - Operator License #: 3746
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/03/05 (Date)
by: BUTCH HOBERECHT (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 2752 Bottom: 2754 T.D. 2765
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 035-24202-0000
Lease Name: KENNEDY
Well Number: 1
Spot Location (QQQQ): 150' N - NE - SW - SW
1140 Feet from North / South Section Line
4290 Feet from East / West Section Line
Sec. 28 Twp. 33 S. R. 8 East West
County: COWLEY
Date Well Completed: 9/07/04
Plugging Commenced: 4/06/2005
Plugging Completed: 4/11/2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MISS	OIL/WATER	0	2754	4 1/2	2754	1335
SURFACE		0	305	8 5/8	305	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 2700', dumped 4 sx. cement on top of sand with dump bailer. Shot off pipe at 1335' and pulled. Run 1" down inside of 8 5/8" surface pipe to 500'. pumped 180 sx. cement down 1", filled to the surface. Pulled out 1" , topped off with cement.

Name of Plugging Contractor: B.P.C. WELL PLUGGING License #: 32475
Address: P.O. BOX 282 BURDEN, KS. 67019

Name of Party Responsible for Plugging Fees: REX H. CAMBERN
State of KANSAS County, SEDGWICK, ss.

REX H. CAMBERN (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) REX H. CAMBERN

(Address) 2332 N. RIDGEFIELD CIR., WICHITA, KS. 67205



SUBSCRIBED and SWORN TO before me this 28 day of April, 2005

Stacy Brown My Commission Expires: 3/24/09
Notary Public

Bm