

API NUMBER 5-29-59

LEASE NAME Veronica

WELL NUMBER 1

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 9S RGE. 25 (E) or (W)

COUNTY Graham

Date Well Completed 5-29-59

Plugging Commenced 4-22-05

Plugging Completed 4-25-05

KCC  
BEM 05  
5-4-05  
RBM/S  
CP 2/3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, S&D, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)  
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? none available

Producing Formation KC Depth to Top \_\_\_\_\_ Bottom RT.D. 4020

00 4022

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Run 127 lbs 2 3/8 open end to 3750' Rig up Allied. This started to take out in fill up. Lay down 1 JT @ 3725. Mix 50 SX 60/40 Poz 10% gel w/200# hulls. Pull tbg to 2710. Mix 50 SX 60/40 Poz 10% gel w/200# hulls. Pull to 1700. Mix 50 SX w/100# hulls - Pull to 675' Circ to surf in 4 1/2 annulus w/20 SX + 100# hulls. Pull tbg out of hole. Tie onto 4 1/2 CS9. Mix 20 SX down CS9. Press to 400#. Shut in CS9. Tie onto surf. pipe - Mix 110 SX Max press 350# shut in w/50#

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address P.O. Box 723 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis Kirner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dennis Kirner

(Address) P.O. Box 723 Hays, KS 67601

SUBSCRIBED AND SWORN to before me this 29<sup>th</sup> day of April, 2005

Marion Sue Weilert  
Notary Public

KCC  
MAY 03 2005  
HAYS, KS

RECEIVED  
MAY - 4 2005  
KCC WICHITA 4-30-06

MARION SUE WEILERT  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 4-30-06

B