

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00368-00-00
Spot: E2NENE Sec/Twnshp/Rge: 22-7S-19W
4620 feet from S Section Line, 330 feet from E Section Line
Lease Name: GROVER Well #: 1
County: ROOKS Total Vertical Depth: 3424 feet

Operator License No.: 9957
Op Name: THOMASON PETROLEUM, INC
Address: 301 W 13TH ST PO BOX 875
HAYS, KS 67601

PROD Size: 5.5 feet: 3411 w/175 sxs cmt
SURF Size: 8.625 feet: 160

\$111²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2005 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE THOMASON Company: THOMASON PETROLEUM, INC. Phone: (785) 625-9045

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
Tubing and packer in the hole at 1396'.
Casing leaks.
Squeeze at 800' - 1200' w/1000 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/05/2005 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 5 1/2" casing with a swedge - pumped 25 sxs neat, followed with 225 sxs mixed with 600# hulls.
Max. P.S.I. 350#. S.I.P. 50#.
Tied onto 8 5/8" - pumped 50 sxs cement.
Max. P.S.I. 150#. S.I.P.0#.

Perfs:

Top	Bot	Thru	Comments
3297	3302		
3296	3305		
3272	3280		

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET 16628.

Plugged through: CSG

District: 04

AD

Signed _____

Pat Staab

(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061564

Form CP-2/3

MAY 06 2005

ANSCHUTZ DRILLING COMPANY #1 GROVER

22-7-19W
E2 NE NE

Contr. ANSCHUTZ DRILLING COMPANY ROOKS County

E 1937RB Comm. 6-21-50 Comp. 8-25-50 IP 143 BOPD & 1/4% WTR

Tops	Depth	Datum	Casing
ANH	1430	+507	8" 160 5" 3411
TOP	2880		
HEEB	3085		GROVER POOL
LANS	3126	-1189	
ARB	3396	-1459	
T.O.D.	3424		

DP 3422, 2 1/2 GO & 2 1/2 GW/
1/2 HR: DD 3424: PB 3320
PERF 19 S, 3 296-3305,
15 S, 3297-3302: ACID
500: 2 BOPH: ACID 3000
PB 3282: PERF 23 S,
3272-80: ACID 500: 4
BOPH: CO 3312: 1 1/2 BOPH
ACID 8000: SWB 5 BOPH
PMP 95 B0/19 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS