

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00511-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 25-3S-24W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FOUGHT Well #: 7
County: NORTON Total Vertical Depth: 3778 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: PO BOX 352 370 W WICHITA AVE
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3775 75 SX CMT
SURF Size: 10.75 feet: 265 160 SX CMT

#12279

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 700# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2005 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Hooked onto 5 1/2" casing - mixed 325 sxs 60/40 pozmix - 10% gel with 700# hulls.
Max. P.S.I. 700#. S.I.P. 500#.
Hooked onto backside and mixed 50 sxs cement.
No pressure - not on vacuum - shut in.

Perfs:

Top	Bot	Thru	Comments
3730	3734		
3688	3692		
3672	3676		
3654	3656		

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Dennis J. Hamel
(TECHNICIAN)

INVOICED

DATE 5-12-05
INV. NO. 2005061557

MAY 04 2005

WOOD RIVER OIL & REFINING #7 FOUGHT

25-3-24W
NW SW SE

Contr. K & E DRLG

NORTON County

E. 2461 RB Comm. Comp. 10-25-57 IP 30 BOPD

Tops	Depth	Datum
LANS	3520	-1059
REAG SND	3771	-1610
TD	3778	-1317


Casing

8" 260

5" 3773

DST 3773-78/1 HR, 800' GAS,
350' OIL, NW, BHP 260#
SWB 3 BOPH

NORTON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NO. 100
0118

INDICEN