

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23622-00-00
Spot: SWNESE Sec/Twnshp/Rge: 36-15S-19W
1900 feet from S Section Line, 905 feet from E Section Line
Lease Name: LEGLEITER Well #: 1
County: ELLIS Total Vertical Depth: 3561 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

PROD Size: 5.5 feet: 3550 w/175 sxs cmt
SURF Size: 8.625 feet: 1148 w/425 sxs cmt

115 73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/04/2005 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 210 sxs 60/40 pozmix - 10% gel - 800# hulls - 15 sxs gel.
Casing parted.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2005 7:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

05/03/2005 - RIH with tubing to 3350' - spotted 40 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled 450' of 5 1/2" casing which parted at this spot.
05/04/2005 - Shot casing at 2665' - casing did not come loose - lost shot gun in the hole.
Shot casing at 2306' - pulled 57 joints total.
RIH with tubing to 1850' - pumped 30 sxs 60/40 pozmix with 150# hulls mixed in.
Pulled tubing to 1650' - pumped 15 sxs gel.
Pulled tubing to 1200' - pumped 50 sxs cement with 250# hulls mixed in.
Pulled tubing to 500' - pumped 90 sxs cement with 100# hulls mixed in to circulate cement to surface.
Hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3532	3538		
3443	3448		
3402	3405		
3379	3382		

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 5-12-05

NO. 2005061555

Form CP-2/3

MAY 06 2005

REPLACEMENT CORE

SLAC: DIAMOND OIL, INC.
1106 E. 27TH, HANCOCK SQ.


#1 LEGLEITER

35-15-19W
SW NE SE

HAYS, KS 67501

CONTR LAWSONCO DRILLING, INC. CITY ELLIS

GEOL _____ FIELD WC(ZIMM SE DISC)



ELV 1959 KB SPD 9/28/83 CARD ISSUED 12/15/83 P 100 BO & 25 BWPD
1954 GL LKC 3380-3446 OA

LOG	Tops	Depth/Datum	API 15-051-23,622
			8 5.8 " 1148: 5 1.2 " 3550
AMH	1145+	814	DST (1) 3315-28 (LKC) 60-60-60-60. REC 60' VSO & GCMW, 60' OIL & GCMW. SIP 1067-1067#, FP 39-48 / 68-78#
TOP	2932-	973	DST (2) 3228-3351 (LKC) 60-60-0-0. REC 60' OIL & GCMW, 120' SO & GCMW (12% OIL, 8% GAS, 38% WTR, 42% MUD), ISIP 1009#, IFP 68-97#
HEEB	3200-	1241	
LANS	3243-	1284	DST (3) 3352-3454 (LKC) 45-45-45-45. 660' GIP. REC 50' OIL & GCM. 60' HO & GCM, 240' FROTHY OIL, SIP 1213-1203#, FP 97-136 / 175-195#
BKC	3484-	1525	
ARB	3531-	1572	MICT - CO. (ARB OH). SWB 30 BWP/2 HRS, NS, SQ'D OH W/ CMT, PF (ARB) 3532-38, W 4 SPF, SWB 10 BOP/3 HRS, 600' OFF BTM, NAT. ONFU 72 BBLS OIH, SET PERMANENT PLUG ABOVE ARB. PF (LKC) 1.3446, 1.3403, 1.3380, AC 1000 C (15% MCA), SWB LD, GSO ONFU 2650' FIH (100% OIL), POP, P 100 BOD & 20% WTR. (ARB OIL PAY REMAINS BEHIND PIPE)
RTD<D	3561-	1602	

CORRECTION: 3 15 84 - CORRECTED FIELD NAME

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

IMAGED