

X 1-18-15-179-30065-00-00¹¹³

6 031220

API NUMBER 15- 1965

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SE, SEC. 11, T. 6 S, R. 27 W/Ex
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5619 5916

Lease Name Adell LKC Well # 102

Operator: Conoco Inc.
Name & Address: Box 267
Great Bend, Ks. 67530

County Sheridan 123.08
Well Total Depth 3787 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well Gas Well Input Well SWD Well
Other well as hereinafter indicated E-8906

RECEIVED
STATE CORPORATION COMMISSION

Plugging Contractor Halliburton Services License Number

JAN 27 1989

Address Oberlin, Ks.

1-27-89
CONSERVATION DIVISION
Wichita, Kansas

Company to plug at: Hour: AM Day: 18 Month: Jan Year: 19 89

Plugging proposal received from David Lorenzo

(company name) Conoco (phone)

were: 8 5/8" set at 237' w/200 sks. 5 1/2" set at 3898' w/250 sks. Perfs
3675' - 3861'. Order 250 sks 65/35 Poz 10% Gel 2% Dical, 50 sks common cement.
500# Hulls. Halliburton Cement Co. LaRue Water Trucks. Chase Well Service.
Holes in casing from 800' to 2000'. Fluid level at 600'. Run tubing to
2070'.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:20PM Day: 18 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ran tubint to 2070'. Tagged fish, mixed and pumped 50 sks
Cement Blend w/3 sks Hulls mixed in followed with 50 sks common cement w/2 sks Hulls
mixed in. Good circulation. Laid down tubing to 600', mixed and pumped 10 bbl. cement
blend slurry to circulate to surface. Laid down tubing, squeezed 4 1/2" casing to
max psi 200# w/total of 154 sks cement blend w/500# Hulls. Squeezed annulus w/146
sks to max psi 150#. Close in 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have supervised this plugging.

DATE 2-02-89

Handwritten initials

Signed Carl Goodrow
Carl Goodrow (TECHNICIAN)

INV. NO. 23825
1-18