

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-20726-00-01  
Spot: NESWSE Sec/Twnshp/Rge: 3-16S-27W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: MENDENHAL Well #: 4  
County: LANE Total Vertical Depth: 4558 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

PROD Size: 5.5 feet: 4510 WITH 200 SX CMT  
SURF Size: feet: 328

# 148<sup>14</sup>

Well Type: SWD UIC Docket No: D21888.0 Date/Time to Plug: 05/06/2005 1:45 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: ROGER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RIH W/TBG TO 1600'. PUMP 400# HULLS & 180 SX CMT TO SURFACE. TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/06/2005 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 1900'. TOC 270'. RUN TUBING TO 1600' & PUMP 60 SX CMT. PUMP 400# HULLS WITH 80 SX CMT. PULL TUBING & TOP OFF WITH 35 SX CMT. CASING HEAD WAS FULL OF CMT & COULD NOT PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
1610	1710		

RECEIVED  
MAY 12 2005  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

MAY - 9 2005  
MP

Signed Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 5-12-05  
WT. NO. 2005061562

Form CP-213