

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-21412-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 1-30S-36W
1250 feet from N Section Line, 1250 feet from E Section Line
Lease Name: HALL Well #: 3-1
County: GRANT Total Vertical Depth: 3100 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

CIBP Size: feet: 2700 WITH 2 SX CMT
PROD Size: 5.5 feet: 3099 WITH 430 SX CMT
SURF Size: 8.625 feet: 640 WITH 315 SX CMT

100²⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/28/2005 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2700' WITH 2 SX CMT. PLUG AT 1645' WITH 25 SX CMT. PLUG AT 670' WITH 25 SX CMT. PLUG AT 40' WITH 10 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK
Date/Time Plugging Completed: 04/28/2005 3:00 PM

WitnessType: COMPLETE (100%)
KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2700' WITH 2 SX CMT ON TOP. 1ST PLUG PUMPED MUD SPACER TO 1650', PUMPED 25 SX CMT INSIDE 5 1/2" CASING. 2ND PLUG PUMPED MUD SPACER TO 670' & PUMP 80 SX CMT TO SURFACE. PRESSURED TO 500 PSIG & SHUT IN. PUMP 30 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 300 PSIG & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2916	2929		
2805	2874		

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

MAY - 4 2005

MP

Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061563

Form CP-2/3