

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21404-00-00
Spot: NENE Sec/Twnshp/Rge: 8-33S-33W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: BRYANT B Well #: 5-8
County: SEWARD Total Vertical Depth: 6170 feet

Operator License No.: 9228
Op Name: MARLIN OIL CORPORATION
Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

CIBP Size: feet: 5588
PROD Size: 5.5 feet: 6124 WITH 175 SX CMT
SURF Size: 8.625 feet: 1520 WITH 700 SX CMT

\$200⁵³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2005 11:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT. PLUG AT 1530' WITH 50 SX CMT. PLUG AT 660' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 02/03/2005 5:00 PM

Witness Type: PARTIAL
KCC Agent: JIM HOLLAND

Actual Plugging Report:

FISH LEFT IN HOLE: TBG ANCHOR @ 5604', 15 JTS/2 3/8" TUBING BELOW ANCHOR TO SEAT NIPPLE @ 6077', 24' MUD ANCHOR. 2/2/05: PUMP 300# HULLS WITH 25 SX CMT TO PLUG PERFS FROM 5570-78'. LOAD CASING WITH MUD. PRESSURE TO 500 PSIG & HELD. 2/3/05: 1ST PLUG PULL OUT OF HOLE TO 1550'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE & PUMP 30 SX CMT. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
6040	6044		
5762	5770		
5737	5750		
5570	5578		

RECEIVED
FEB 22 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2423' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE 5-11-05
INV. NO. 2005061546

Form 23

Bm