

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25408-00-00
Spot: N2N2 Sec/Twnshp/Rge: 29-11S-19W
680 feet from N Section Line, 2550 feet from W Section Line
Lease Name: IRENE Well #: 29-1
County: ELLIS Total Vertical Depth: 3754 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 900 N TYLER ROAD #14
WICHITA, KS 67212

SURF Size: 8.625 feet: 219

A 122⁰¹

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/03/2005 10:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: NONE
Date/Time Plugging Completed: 05/04/2005 1:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

1st. Plug at 2000' w/25 sxs.
2nd. Plug at 1450' w/25 sxs.
3rd. Plug at 750' w/100 sxs.
4th. Plug at 225' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

AD

Signed

Dennis J. Hamel

(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061559

Form CP-2/3

MAY 09 2005