

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15237-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 3-17S-11W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BURMEISTER (FREES) Well #: 13  
County: BARTON Total Vertical Depth: 3333 feet

Operator License No.: 6239  
Op Name: ZINSZER OIL CO., INC.  
Address: PO BOX 211  
HAYS, KS 67601

PROD Size: 7 feet: 3320 250 SX  
SURF Size: 13 feet: 317

#108<sup>32</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/27/2005 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: PERRY S. HENMAN Company: ZINSZER OIL CO., INC. Phone: (785) 625-9448

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/29/2005 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

04/27/2005 - Sanded to 3291' and dumped 7 sxs cement.  
Perforated at 1350'.  
Pumped 150 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
Well on vaccum.  
Perforated at 280'.  
Pumped 50 sxs gel with 1000# hulls.  
Pumped 150 sxs cement.  
Max. P.S.I. 200#. S.I.P. 50#.  
04/28/2005 - Tagged cement at 700'. Fluid at 50'.  
Pumped 180 sxs cement down backside.  
Circulated inside 7" with 120 sxs cement.  
04/29/2005 - Tagged cement at 240'.  
Circulated with 60 sxs cement.  
Hole stayed full.

RECEIVED  
MAY 12 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

110

Signed Case Morris  
(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061565

MAY 06 2005