

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21769-00-01
Spot: SENESE Sec/Twnshp/Rge: 20-17S-24W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: GERSTNER C Well #: 3
County: NESS Total Vertical Depth: 4401 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH STREET
NEWTON, KS 67114

PROD Size: 5.5 feet: 4401 WITH 150 SX CMT
SURF Size: feet: 294 WITH 190 SX CMT

#143⁰³

Well Type: EOR UIC Docket No: E19943.1 Date/Time to Plug: 05/06/2005 10:30 AM

Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RIH W/TUBING TO 1170'. PUMP 500# HULLS FOLLOWED BY 150 SX CMT TO SURFACE. TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/06/2005 11:45 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

RAN 2 3/8" TUBING TO 1200'. MIX & PUMP 170 SX CMT WITH HULLS. CMT CIRCULATED TO SURFACE. TOP OFF WITH 30 SX CMT. TESTED ANNULUS TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
1175	1370		

RECEIVED
MAY 12 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

MAY - 9 2005

MD

Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061562