

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-00024-00-00  
Spot: SESW Sec/Twnshp/Rge: 10-31S-37W  
660 feet from S Section Line, 1976 feet from W Section Line  
Lease Name: MCCREARY Well #: 2-10  
County: STEVENS Total Vertical Depth: 6139 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA,  
Address: 5205 N. O'CONNOR BLVD.  
IRVING, TX 75039

CIBP Size: feet: 2810 WITH 4 SX CMT  
PROD Size: 8.625 feet: 3061 WITH 500 SX CMT  
SURF Size: 13.38 feet: 578 WITH 500 SX CMT

*\$199<sup>52</sup>*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2005 11:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2810' WITH 4 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 600' WITH 75 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 04/27/2005 2:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2810' WITH 4 SX CMT ON TOP. 1ST PLUG PUMP MUD SPACER TO 1650'. CHECK WITH WIRELINE. PUMP 50 SX CMT AT 1650' INSIDE 8 5/8". 2ND PLUG PULL OUT OF HOLE TO 600'. LOAD HOLE WITH MUD. PUMP 75 SX CMT AT 600'. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 20 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2847	2918		

RECEIVED  
MAY 12 2005  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 924' OF 8 5/8" CASING.

Plugged through: CSG

District: 01

MAY - 4 2005

*MP*

Signed

*Jim Holland*  
PIRTH  
(TECHNICIAN)

INVOICED

DATE 5-12-05

INV. NO. 2005061563

Form CP-2/3